BRUHAT BENGALURU MAHANAGARA PALIKE

Name of Work: Improvements To Footpaths In Cross Roads of Kempapura In Ward No-10

Modified Schudule-B

Sl No	Description of work	Unit	Qty	Rate	Rs in Words
1	Removing and resetting of Footpath Slab (Approved Rate)	SQm	0.00	100.00	Rupees One Hundred Only
2	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete as per specifications and directions of the Engineer in charge.	Cum	225.00	120.00	Rupees One Hundred Twenty Only
	Above 125%	Cum	131.33	120.00	Rupees One Hundred Twenty Only
3	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately)Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregates	Cum	30.00	5800.00	Rupees Five Thousand Eight Hundred Only
	Above 125%	Cum	20.45	5800.00	Rupees Five Thousand Eight Hundred Only
4	Removing And Resetting Of Kerb Stone[Approved Arrival Rate]	M	142.00	100.00	Rupees One Hundred Only
5	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately)M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	CUm	51.98	6000.01	Rupees Six Thousand And Paise One Only
6	Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications. Section 1600 & 2200	Tn	3.12	95000.00	Rupees Ninety Five Thousand Only
7	Providing And Fixing Precast Covering Slab Made Out Of CC 1;2;4 With 10cm Thick And Finishimg Cutting Including Form Work Curing Including Cost Of All Materials, Labour,Hire Charges Of Machinery,Loading,Unloading,Lead And Lift,Transportation Etc[Data Rate]	Sqm	222.84	2000.00	Rupees Two Thousand Only
8	Supplying and filling in plinth with sand under floors, foundation of Bridges including watering, ramming, consolidating and dressing complete.	Cum	0.00	2000.00	Rupees Two Thousand Only

ಕಾ.ಅ. (ಬ್ಯಾ.ವಿ.)
ಬೃ.ಬೆಂ.ಮ.ಪಾ.

Scanned with CamScanner

9	Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per m2 over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level , including cost of materials, labour and Usage charges of machinery complete as per specifications	Sqm	298.08	971.90	Rupees Nine Hundred Seventy One And Paise Ninety Only
10	Supplying and fixing M15 grade precast cement concrete 600 x 300 x 150 mm Kerb Stone for Roadway, Sidewalls and gutters fixed with CM 1:3 fixed and finsihed in line as per direction of Engineer in charge.	Mtr	309.00	350.00	Rupees Three Hundred Fifty Only
11	Painting Two Coats on New Concrete Surfaces Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces.	Sqm	157.85	100.00	Rupees One Hundred Only
12	Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 14 m3)	Cum	202.50	50.00	Rupees Fifty Only
	Above 125%	Cum	153.83	50.00	Rupees Fifty Only
13	Cost of Haulage Excluding Loading and UnloadingTaking output 18 t load and lead 10 km = 180 t.km t	t.Km	259.20	84.99	Rupees Eighty Four And Paise Ninety Nine Only
	Above 125%	t.Km	196.90	84.99	Rupees Eighty Four And Paise Ninety Nine Only
	EIRL				
E1	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately)Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates	Cum	36.26	4936.40	Rupees Four Thousand Nine Hundred Thirty Six And Paise Forty Only

C. Ramesh

ಕಾರ್ಯ. (ದಕ್ಷಿಣ)
Executive Engineer
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
BBMP

Scanned with CamScanner